7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of quantities for restoring Katenhalli tank, registered No. 46 of Gudibanda Sub-Taluk.

Items of work	Per	Quantity
Bund—		
Earthwork with watering and tamping	C. yd.	8,801
Examining and closing leaks in the bund near right return	Lump	sum
Turfing	S. yd.	6,783
Old stone work with new jelly	C. yd.	200
New stone work	"	759
Gravel backing	"	241
Providing new grade stones with chiselling and painting	Each	30
Providing Index stones	"	30
Do B. M. stones	"	2
Do gauge stone	"	1
Do Registered No. stone	"	1
Do date stone	"	1
Clearing jungle, etc., sluice	Lump	sum
Examining and repairing weir	"	1 0
Earthwork excavation	C. yd.	81
Burnt brick in surki mortar	C. ft.	678
Surki plastering	Sq.	803
Burnt stone slabs	S. ft.	280
Rough stone work, new	C. yd.	77
Draft clearing	"	104
Blastering rock	"	10
Providing joggles	Each	20

V. V. KARVE,
Executive Engineer.

TUMKUR DISTRICT.

Abstract Notification.

Attention of the public is invited to page 747 of Part IV of *Mysore Gazette*, dated 15th August 1918, calling for tenders for constructing cows' shed and calfs' shed at Kunigal. The last date for tender is 26th August 1918, and the earnest money is Rs. 300.

Abstract Notification.

Attention of the public is invited to pages 747—748 of Part IV of *Mysore Gazette* dated 15th August 1918, calling for tenders for constructing Sub-Registrar's Office and Bonded Warehouse at Maddagiri. The last date for tender is 26th August 1918. Earnest money to accompany tender is Rs. 150.

TUMKUR DIVISION.

Dated 8th August 1918.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, up to 20th September 1918, for restoring Jindagere Tank, Registered No. 376 Gubbi Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1919.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Tumkur, between the hours of 11 A.M. and 5 P.M., except Sundays and holidays.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred only (Rs. 200) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Jindagere Tank, Registered No. 376, Gubbi Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of quantities for restoring the Jindagere Tank, Registered No. 376 of Gubbi Taluk.

Items of work	Per	Quantity
Earthwork including watering and tamping (earth available to be used to bund)	C. yd.	4,904
Gravel backing behind revetment	"	872
Excavating foundation for revetment and using the same to bund	"	1,205
Rough stone revetment	"	1,607
Turfing	S. yd.	5,784
Grade stones with bed slabs including cutting figures and painting	Each	35
Index stones	"	25
B. M. stones including cutting figures and painting	"	3
Register number stones do	"	11
Gauge stone including. do	"	1
Clearing jungle shrubs, big honge and other trees	L. S. Rs.	
Sluice.		
Earthwork excavation and usinglit to bund	C. yd.	49
Concrete with surki mortar	C. ft.	41
Burnt brick in surki mortar	"	227
Burnt stone slabs with one line dressing	S. ft.	109
Plastering with surki mortar	Sq.	1'63
Cutting orifice and fixing wooden plug with iron rod, lock and key, etc., complete	L. S. Rs.	
Iron pipe 10" dr. including carting, fixing, etc., complete	R. ft.	45
Waste weir.		
Earthwork excavation	C. yd.	1,225
Burnt brick in surki mortar	C. ft.	682
Burnt stone slabs dressed	S. ft.	455
Plastering with surki mortar	Sq.	3'43
Rough stone work	C. yd.	157
Turfing	S. yd.	37

N. G. KRISHNA IYENGAR,
Executive Engineer.

NEW PALACE DIVISION.

Sealed tenders will be received in the office of the Architectural Executive Engineer, New Palace Division, at Nazarbad, in the City of Mysore, on or before Monday the 2nd September 1918, for the supply of Rolled Steel Girders (British or American Make) as per list hereto appended.

The whole quantity as per list is required to be delivered F. O. R., Mysore, before the end of April 1919, for which the rate per cwt. should be quoted.

If, on account of the uncertain conditions of the market for steel goods any difficulty as regards freight or Government restriction is apprehended, the bidders may quote their rate for delivery, subject to their obtaining the necessary freight and Government Permission in regard to which arrangements will be made officially to procure the necessary Priority Certificate, in favour of the firm whose tender will be accepted and for the quantity included in the tender.

List of Rolled Steel Girders required.

No.	Length	Section		
		Depth	Width of flange	Weight per R.ft.
5	34'—0"	24"	7½"	100 lbs.
1	28'—0"	24"	7½"	100 "
14	34'—0"	20"	7½"	89 "
4	34'—0"	18"	7"	75 "
2	28'—0"	18"	7"	75 "
18	26'—0"	16"	6"	62 "
16	16'—0"	16"	6"	63 "
8	24'—0"	15"	5"	42 "
3	18'—0"	12"	5"	32 "
Total ... 71				

S. H. LAKSHMINARASAPPA,
Architectural Executive Engineer,
In charge of New Palace Division, Mysore.

HASSAN DIVISION.

Abstract Notification.

The attention of the public is invited to the Notification dated 27th July 1918, published on page 722 of Part IV of 32nd issue of *Mysore Gazette*, wherein tenders for constructing a combined building for the Sub-Registrar's Office and Bonded Warehouse at Hole-Narsipur.

R. W. SCALDWELL,
Executive Engineer.